# DATA SHEET

# 74ALS251

8-input multiplexer (3-State)

Product specification
IC05 Data Handbook

1991 Feb 08







Philips Semiconductors Product specification

# 8-input multiplexer (3-State)

74ALS251

#### **FEATURES**

- 8-to-1 multiplexing
- On chip decoding
- Multifunction capability
- Inverting and non-inverting outputs
- Both outputs are 3-State for further multiplexer expansion

#### **DESCRIPTION**


The 74ALS251 is a logic implementation of a single 8-position switch with the switch position controlled by the state of three select (S0, S1, S2) inputs. True (Y) and complementary  $(\overline{Y})$  outputs are both provided.

The output enable ( $\overline{OE}$ ) is active Low. When  $\overline{OE}$  is High, both outputs are in High impedance state, allowing multiple connections to a common bus without driving nor loading the bus significantly.

When the outputs of more than one device are tied together, the user must ensure that there is no overlap in the active-Low portion of the output enable voltages in order to avoid high currents that could exceed the maximum current rating.

TYPE	TYPICAL PROPAGATION DELAY	TYPICAL SUPPLY CURRENT (TOTAL)
74ALS251	7.0ns	7.5mA

#### **PIN CONFIGURATION**



#### **ORDERING INFORMATION**


	ORDER CODE		
DESCRIPTION	COMMERCIAL RANGE $V_{CC}$ = 5V ±10%, $T_{amb}$ = 0°C to +70°C	DRAWING NUMBER	
16-pin plastic DIP	74ALS251N	SOT38-4	
16-pin plastic SO	74ALS251D	SOT109-1	

## INPUT AND OUTPUT LOADING AND FAN-OUT TABLE


PINS	DESCRIPTION	74ALS (U.L.) HIGH/LOW	LOAD VALUE HIGH/LOW
10 – 17	Data inputs	1.0/1.0	20μA/0.1mA
S0 – S2	Select inputs	1.0/1.0	20μA/0.1mA
ŌĒ	Output Enable input (active-Low)	1.0/1.0	20μA/0.1mA
Y, \overline{\tau}	Data outputs	130/240	2.5mA/24mA

NOTE: One (1.0) ALS unit load is defined as: 20μA in the High state and 0.1mA in the Low state.

# LOGIC SYMBOL



### **IEC/IEEE SYMBOL**




Philips Semiconductors Product specification

# 8-input multiplexer (3-State)

74ALS251

# **LOGIC DIAGRAM**



# **FUNCTION TABLE**

	INP	OUTF	PUTS		
S2	S1	Υ	Y		
Х	Х	Х	Н	Z	Z
L	L	L	L	10	Ī0
L	L	Н	L	l1	Ī1
L	Н	L	L	12	Ī2
L	Н	Н	L	13	Ī3
Н	L	L	L	14	Ī4
Н	L	Н	L	15	Ī5
Н	Н	L	L	16	Ī6
Н	Н	Н	L	17	Ī7

H = High voltage level L = Low voltage level

X = Don't care Z = High impedance "off" state

# **ABSOLUTE MAXIMUM RATINGS**

(Operation beyond the limit set forth in this table may impair the useful life of the device. Unless otherwise noted these limits are over the operating free air temperature range.)

SYMBOL	PARAMETER	RATING	UNIT
V <sub>CC</sub>	Supply voltage	-0.5 to +7.0	V
$V_{IN}$	Input voltage	-0.5 to +7.0	V
I <sub>IN</sub>	Input current	−30 to +5	mA
V <sub>OUT</sub>	Voltage applied to output in High output state	−0.5 to V <sub>CC</sub>	V
I <sub>OUT</sub>	Current applied to output in Low output state	48	mA
T <sub>amb</sub>	Operating free-air temperature range	0 to +70	°C
T <sub>stg</sub>	Storage temperature range	-65 to +150	°C

# **RECOMMENDED OPERATING CONDITIONS**

SYMBOL	PARAMETER		UNIT		
STWIBOL	PARAINETER	MIN	NOM	MAX	UNIT
V <sub>CC</sub>	Supply voltage	4.5	5.0	5.5	V
$V_{IH}$	High-level input voltage	2.0			V
$V_{IL}$	Low-level input voltage			0.8	V
I <sub>IK</sub>	Input clamp current			-18	mA
I <sub>OH</sub>	High-level output current			-2.6	mA
I <sub>OL</sub>	Low-level output current			24	mA
T <sub>amb</sub>	Operating free-air temperature range	0		+70	°C

Philips Semiconductors Product specification

# 8-input multiplexer (3-State)

74ALS251

#### DC ELECTRICAL CHARACTERISTICS

(Over recommended operating free-air temperature range unless otherwise noted.)

CVMDOL	DADAMETER	TECT CONDIT	IONE1		LIMITS			
SYMBOL	PARAMETER	TEST CONDITI	TEST CONDITIONS <sup>1</sup>			MAX	UNIT	
V	High lovel output valtage	V <sub>CC</sub> ±10%, V <sub>IL</sub> = MAX,	$I_{OH} = -0.4$ mA	V <sub>CC</sub> - 2			V	
V <sub>OH</sub>	High-level output voltage	V <sub>IH</sub> = MIN	$I_{OH} = -2.6$ mA	2.4	3.2		V	
V	Low lovel output voltage	$V_{CC} = MIN, V_{IL} = MAX,$	I <sub>OL</sub> = 12mA		0.25	0.40	V	
V <sub>OL</sub>	Low-level output voltage	V <sub>IH</sub> = MIN	I <sub>OL</sub> = 24mA		0.35	0.50	V	
V <sub>IK</sub>	Input clamp voltage	$V_{CC} = MIN, I_I = I_{IK}$	$V_{CC} = MIN, I_I = I_{IK}$			-1.5	V	
I <sub>I</sub>	Input current at maximum input voltage	$V_{CC} = MAX, V_I = 7.0V$				0.1	mA	
I <sub>IH</sub>	High-level input current	$V_{CC} = MAX, V_I = 2.7V$	$V_{CC} = MAX, V_I = 2.7V$			20	μΑ	
I <sub>IL</sub>	Low-level input current	$V_{CC} = MAX, V_I = 0.4V$				-0.1	mA	
I <sub>OZH</sub>	Off-state output current, High-level voltage applied	$V_{CC} = MAX, V_I = 2.7V$				20	μА	
I <sub>OZL</sub>	Off-state output current, Low-level voltage applied	$V_{CC} = MAX, V_I = 0.4V$				-20	μА	
I <sub>O</sub>	Output current <sup>3</sup>	$V_{CC} = MAX, V_O = 2.25V$		-30		-112	mA	
1	Supply current (total)	\/ <b>- N</b> AAY			7.0	10	mA	
Icc	I <sub>CCZ</sub>	ACC = INIVY	V <sub>CC</sub> = MAX		9.0	14	mA	

# NOTES:

- 1. For conditions shown as MIN or MAX, use the appropriate value specified under recommended operating conditions for the applicable type.
- All typical values are at V<sub>CC</sub> = 5V, T<sub>amb</sub> = 25°C.
   The output conditions have been chosen to produce a current that closely approximates one half of the true short-circuit output current, I<sub>OS</sub>.

# **AC ELECTRICAL CHARACTERISTICS**

			LIM		
SYMBOL	PARAMETER	TEST CONDITION	T <sub>amb</sub> = 0°C V <sub>CC</sub> = +5. C <sub>L</sub> = 50pF,	0V ± 10%	UNIT
			MIN	MAX	
t <sub>PLH</sub> t <sub>PHL</sub>	Propagation delay In to Y	Waveform 2	4.0 4.0	12.0 12.0	ns
t <sub>PLH</sub> t <sub>PHL</sub>	Propagation delay In to $\overline{Y}$	Waveform 1	3.0 6.0	10.0 15.0	ns
t <sub>PLH</sub> t <sub>PHL</sub>	Propagation delay Sn to Y	Waveform 1, 2	5.0 7.0	15.0 16.0	ns
t <sub>PLH</sub> t <sub>PHL</sub>	Propagation delay Sn to Y	Waveform 1, 2	8.0 5.0	17.0 15.0	ns
t <sub>PZH</sub> t <sub>PZL</sub>	Propagation delay OE to Y	Waveform 3 Waveform 4	2.0 3.0	8.0 9.0	ns
t <sub>PHZ</sub> t <sub>PLZ</sub>	Propagation delay OE to Y	Waveform 3 Waveform 4	2.0 1.0	8.0 7.0	ns
t <sub>PZH</sub> t <sub>PZL</sub>	Propagation delay OE to Y	Waveform 3 Waveform 4	2.0 3.0	8.0 9.0	ns
t <sub>PHZ</sub> t <sub>PLZ</sub>	Propagation delay OE to Y	Waveform 3 Waveform 4	2.0 1.0	8.0 7.0	ns


Philips Semiconductors Product specification

# 8-input multiplexer (3-State)


74ALS251

#### **AC WAVEFORMS**


For all waveforms,  $V_M = 1.3V$ .




Waveform 1. Propagation Delay for Inverting Output



Waveform 2. Propagation Delay for Non-inverting Output




Waveform 3. 3-State Output Enable Time to High Level and Output Disable Time from High Level



Waveform 4. 3-State Output Enable Time to Low Level and Output Disable Time from Low Level

# **TEST CIRCUIT AND WAVEFORMS**



**Test Circuit for 3-State Outputs** 

## **SWITCH POSITION**

TEST	SWITCH
$t_{PLZ}, t_{PZL}$	closed
All other	open


## **DEFINITIONS:**

R<sub>L</sub> = Load resistor;

see AC electrical characteristics for value.

 $C_L = Load$  capacitance includes jig and probe capacitance; see AC electrical characteristics for value.

 $R_T$  = Termination resistance should be equal to  $Z_{OUT}$  of pulse generators.



# **Input Pulse Definition**

Eamily		INPUT	PULSE RE	QUIREN	MENTS	
Family	Amplitude	$V_{\text{M}}$	Rep.Rate	t <sub>w</sub>	t <sub>TLH</sub>	t <sub>THL</sub>
74ALS	74ALS 3.5V 1.3V		1MHz	500ns	2.0ns	2.0ns

SC00072


Product specification

# 8-input multiplexer (3-State)

74ALS251

DIP16: plastic dual in-line package; 16 leads (300 mil)

SOT38-4



# DIMENSIONS (inch dimensions are derived from the original mm dimensions)

UNIT	A max.	A <sub>1</sub> min.	A <sub>2</sub> max.	b	b <sub>1</sub>	b <sub>2</sub>	O	D <sup>(1)</sup>	E <sup>(1)</sup>	e	e <sub>1</sub>	L	ME	Мн	w	Z <sup>(1)</sup> max.
mm	4.2	0.51	3.2	1.73 1.30	0.53 0.38	1.25 0.85	0.36 0.23	19.50 18.55	6.48 6.20	2.54	7.62	3.60 3.05	8.25 7.80	10.0 8.3	0.254	0.76
inches	0.17	0.020	0.13	0.068 0.051	0.021 0.015	0.049 0.033	0.014 0.009	0.77 0.73	0.26 0.24	0.10	0.30	0.14 0.12	0.32 0.31	0.39 0.33	0.01	0.030

10 mm

#### Note

1. Plastic or metal protrusions of 0.25 mm maximum per side are not included.

OUTL	INE		REFER	RENCES	EUROPEAN	ISSUE DATE
VERS	ION	IEC	JEDEC	EIAJ	PROJECTION	
ѕотз	8-4					<del>92-11-17</del> 95-01-14


Product specification

# 8-input multiplexer (3-State)

74ALS251

# SO16: plastic small outline package; 16 leads; body width 3.9 mm

SOT109-1



## DIMENSIONS (inch dimensions are derived from the original mm dimensions)

_	·										,								
	UNIT	A max.	Α1	A <sub>2</sub>	A <sub>3</sub>	bp	С	D <sup>(1)</sup>	E <sup>(1)</sup>	е	HE	L	Lp	O	v	w	у	Z <sup>(1)</sup>	θ
	mm	1.75	0.25 0.10	1.45 1.25	0.25	0.49 0.36	0.25 0.19	10.0 9.8	4.0 3.8	1.27	6.2 5.8	1.05	1.0 0.4	0.7 0.6	0.25	0.25	0.1	0.7 0.3	8°
i	inches	0.069	0.0098 0.0039	0.057 0.049	0.01		0.0098 0.0075	0.39 0.38	0.16 0.15	0.050	0.24 0.23	0.041	0.039 0.016	0.028 0.020	0.01	0.01	0.004	0.028 0.012	0°

#### Note

1. Plastic or metal protrusions of 0.15 mm maximum per side are not included.

OUTLINE		REFER	EUROPEAN	ISSUE DATE			
VERSION	IEC	JEDEC	EIAJ		PROJECTION	ISSUE DATE	
SOT109-1	076E07S	MS-012AC				<del>91-08-13</del> 95-01-23	

Philips Semiconductors Product specification

# 8-input multiplexer (3-State)

74ALS251

DEFINITIONS							
Data Sheet Identification	Product Status	Definition					
Objective Specification	Formative or in Design	This data sheet contains the design target or goal specifications for product development. Specifications may change in any manner without notice.					
Preliminary Specification	Preproduction Product	This data sheet contains preliminary data, and supplementary data will be published at a later date. Philips Semiconductors reserves the right to make changes at any time without notice in order to improve design and supply the best possible product.					
Product Specification	Full Production	This data sheet contains Final Specifications. Philips Semiconductors reserves the right to make changes at any time without notice, in order to improve design and supply the best possible product.					

Philips Semiconductors and Philips Electronics North America Corporation reserve the right to make changes, without notice, in the products, including circuits, standard cells, and/or software, described or contained herein in order to improve design and/or performance. Philips Semiconductors assumes no responsibility or liability for the use of any of these products, conveys no license or title under any patent, copyright, or mask work right to these products, and makes no representations or warranties that these products are free from patent, copyright, or mask work right infringement, unless otherwise specified. Applications that are described herein for any of these products are for illustrative purposes only. Philips Semiconductors makes no representation or warranty that such applications will be suitable for the specified use without further testing or modification.

#### LIFE SUPPORT APPLICATIONS

Philips Semiconductors and Philips Electronics North America Corporation Products are not designed for use in life support appliances, devices, or systems where malfunction of a Philips Semiconductors and Philips Electronics North America Corporation Product can reasonably be expected to result in a personal injury. Philips Semiconductors and Philips Electronics North America Corporation customers using or selling Philips Semiconductors and Philips Electronics North America Corporation Products for use in such applications do so at their own risk and agree to fully indemnify Philips Semiconductors and Philips Electronics North America Corporation for any damages resulting from such improper use or sale.

Philips Semiconductors 811 East Arques Avenue P.O. Box 3409 Sunnyvale, California 94088–3409 Telephone 800-234-7381

**Philips** 

Semiconductors

© Copyright Philips Electronics North America Corporation 1997 All rights reserved. Printed in U.S.A.

Let's make things better.



